



# **TEST PLUG HYDROSTATIC 2" SCH XXS SPECIAL**

## **Dimensions**

Lifting/ Transportation...... Transportation on pallet

## Construction year

Built...... 2019

#### Area of use / certification

Onshore/offshore...... Offshore

## **Type**

#### Flow / Pressure / Volume

P-max (bar):	534	P-max (PSI)	2250
Nominal Pipe Size (Inches)		, ,	
Nominal Pipe Schedule	XXS		
Plug Outside Ø (mm)	36.3		
Plug Length (mm)	232		
Max Upstream pressure (bar):	103.0		
Minimum temp. (GrC)	-23		
Max temp. (GrC)	82		

## Additional information

Equipment / Functions....... Compatible Test Media: Water, Air, Glycol (Low Temperature Applications)

Installation:

Use GTRP installation tool when installing plug. GTRP-INST-050-13

Normal Installation Torque : 34 Nm Maximum Installation Torque : 54 Nm

Eliminate concerns over inadequate joint strength when pressure testing welded flange connections.

Previous flange weld testing devices have been shown to apply only radial and hoop stresses to the weld location. Use of these devices for pressure testing will not adequately test or verify the longitudinal strength of the flange-to-pipe weld

- The plug and test flange act independently of each other so that the weld joint is subjected to real world stresses during pressure testing
- Flange to pipe welds are tested without needing to pressurize the entire system
- Available for pipe sizes ranging from 2" to 12" (DN50 DN300). Larger sizes available upon request.

### FEATURES & BENEFITS:

- Real World Service Conditions Provides a solution where the weld joint is subjected to 100% of the hydrotest stress radial, hoop and longitudinal Test simulates.
- Sizes from 2" through 14" NPS from stock larger or smaller sizes available.
- High Performance Working pressures to 2,250 psig (154 Barg) higher pressures available
- Safer Uses proven GripTight self gripping action
- Reduce Cost Uses a minimal amount of water per test